



The Bhagirathi Cooperative Milk Producers' Union Limited

NOTICE INVITING TENDER

BU/ENGG/CIVIL/1068

Dated: 30/07/2021

The Bhagirathi Cooperative Milk Producers' Union Limited invites tender in **two bid** system from reputed contractors for the repairing and renovation work of floor, paneer cold store room at Bhagirathi Milk Union campus, feeder dairy ,panchanantala ,Berhampore ,Murshidabad.

IMPORTANT DATE AND TIME SCHEDULE

Sl. No.	Particulars	Date & Time
1	Date of Inviting NIT	30.07.2021 at 1500 hrs
2	Tender Submission Start Date	31.07.2021 at 1500 hrs
3	Tender Submission End Date	09.08.2021 by 1500 hrs
4	Bid Opening Date	To be notified later

The details of work are given below:

Nature of Work	Repairing & renovation of paneer cold store room.(Civil Work)
Scope of Work	As per Annexure – A
Estimated Cost of Work	Rs. 1,18,008.00/- (approx)
Bid Inviting Authority	The Managing Director of The Bhagirathi Cooperative Milk Producers' Union Limited
Earnest Money Deposit (EMD)	Rs. 2360/- in Demand Draft in favour of The Managing Director of The Bhagirathi Cooperative Milk Producers' Union Limited payable at Berhampore.
Technical Bid	1. GST Document 2. PAN Card 3. Trade License
Bid Document	The bid document is available in the official website of The Bhagirathi Milk Union www.bhagirathimilk.com
Financial Bid	The financial bid documents of the technically qualified bidders will only be opened. Rate shall be quoted in the Financial bid. The rate quoted by the tender shall be inclusive of all taxes and levies.
Award of Contract (AOC)	The bidder selected after evaluation of financial bid by the Tender Committee will be given Award of Contract after approval from Competent Authority, subject to fulfillment of Terms and Conditions provided in the tender.
Validity of Bid	180 days after opening of Tender
Important Instructions	Technical bid shall be submitted in a separate sealed cover. Similarly,

	<p>Financial bid also will be submitted in a separate sealed cover. Both the covers of Technical and financial bid shall be kept in a larger sealed cover superscribing Tender reference No.</p> <p>This sealed cover should be submitted at the Receive & Dispatch Section of the Bhagirathi Cooperative Milk Producers Union Limited at Berhampore, Murshidabad within stipulated time and date.</p> <p>Address: The Managing Director, Bhagirathi Co-op. Milk Producers' Union Ltd. Feeder Dairy: P.O-Chaltia : PIN -742165: Dist.-Murshidabad</p> <p>Taxes will be deducted as per Govt. norms</p>
--	--

GENERAL TERMS AND CONDITIONS:

1. Any conditional or incomplete Tender shall not be accepted.
2. The successful Tender must commission the work within a period of 7 days from the date of issue of Work order.
3. The rate quoted is inclusive of all labour and material required for the Job. The Tender involves scope of supply and service.
4. No escalation in price / rate will be allowed on any ground and no claim in this regard shall be entertained.
5. EMD of the lowest bidder who has been awarded with the Contract shall be converted into Security deposit and shall be released after successful completion of the Work duly approved by the Competent Authority. EMD of unsuccessful bidders shall be released within 1 month after the AOC has been awarded to the lowest bidder. EMD shall not carry any interest.
6. No mobilization advance shall be given for this contract at any cost.
7. All the rates quoted by the Tender must be inclusive of all required materials in adherence to schedule of job as furnished in the Tender.
8. Terms of Payment: The payment shall be released in two phases:
 - a. 90% payment shall be made within 30 days after successful completion of the job duly certified by the departmental head and approved by competent authority.
 - b. 10% payment shall be made after 12 months of successful completion of the job. This 10% shall serve as performance guarantee. In case there the work is found to be faulty due to negligence or use of inferior quality material by the contractor which is found after release of 90% payment the performance guarantee shall be forfeited and the contractor shall straight be blacklisted for 3 years.

9. Payment will only be made in NEFT/RTGS after Approval from Competent Authority. Three copies of invoices must be submitted for payment.
10. Liquidated damage: Liquidated damage of minimum 0.5% per day of the total Order awarded to the bidder shall be charged if there is any delay in completion or inception of the job subjected to a maximum of 10% and the cost shall be recovered from the Contractor by deducting from the bills.
11. If the tender has already been blacklisted by any Government/ Government Undertakings/ Co-operative societies, his tender will be rejected. In case information about such black listing comes to the knowledge of the Union after awarding of the tender, the contract will be terminated, liquidated damages levied, apart from taking penal action.
12. BCMPUL reserves the right to accept or reject any or all tender wholly / partly at any point of time without assigning any reason thereof.
13. Force Majeure: For any delay in job not attributable to the Contractor and the Milk Union shall be termed as Liquidated damage such as war, lockouts, catastrophe or any act of God. No liquidated damage on account of the Contractor shall be deducted for this clause.
14. Successful bidder has to complete the work within 30 days
15. For any disputes between the Milk Union and Contractor the decision of the Milk Union shall be the final binding.

Precautions:

1. The tender must perform site inspection and the requirement of the Union before submitting his tender.
2. The person signing the tender should be the Proprietor / Partner / Managing Director or any other person duly authorized to sign the tender document. In the latter case, authorization letter should be attached.

Managing Director
The Bhagirathi Co-operative Milk
Producers' Union Limited

Copy forwarded to:

1. Office Notice Board
2. Office Copy
3. Website (www.bhagirathimilk.com)

FINANCIAL BID

I(bidder) abide by all the terms and conditions of this NIT and submit financial offer below:

Item Description	Basic Rate (in Rs.)	Taxes and other levies (Rs.)	Total Amount (in Rs.)
Civil works as per (Annexure – A)	To be quoted by the bidder	To be quoted by the bidder	To be quoted by the bidder

Thanking you,

Signature of the bidder

(NAME IN CAPITAL LETTER)

ANNEXURE – A

ESTIMATE FOR THE REPAIRING & RENOVATION OF FLOOR IN PANEER COLD STORE ROOM			
AT BHAHIRATHI MILK UNION CAMPUS BERHAMPORE MURSAHIDABAD			
SCHEDULE OF RATES: PWD(WB), SCHEDULE OF RATES BUILDING & SANITARY W.E.F 01.01.2017, MURSHIDABAD			
SL NO	DESCRIPTIONS OF WORKS	QUANTITY	UNIT
1	Dismantling all types of masonry excepting cement concrete plain or reinforced, stacking serviceable materials at site and removing rubbish as directed within a lead of 75 m. 8.23 x 7.00 x 0.100 = 5.761 m ³ , 30.46 x 0.304 x 0.050= 0.462m ³	6.223	Cu.m
2	Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement,if any, in ground floor as per relevant IS codes. a) Pakur Variety i)8.23 x 7.00 x 0.100 = 5.761 m ³	5.761	Cu.m
3	18 mm. to 22 mm. thick, kota stone slab set in 20 mm thick (avg) cement mortar (1:4) in floor, stair & lobby including pointing in cement slurry with admixture of pigment matching the stone shade, including grinding & polishing as per direction of Engineer - in - charge to match with the existing work. [Slurry for bedding @ 4.4 kg/Sq.m and pointing @2.0 kg/Sq.m] i)8.23 x 7.00 =57.61m ³ , ii) (8.23 x 0.304)x2= 5.00 m ² , iii) (7 x 0.304)x2= 4.25 m ²	66.860	Sq.M
4	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] (ii) With 1:4 cement mortar (b) 15 mm thick plaster , 4.23 x 2.74 x 2 =23.180 m ²	23.180	Sq.M
5	(A) Providing and fixing of false ceiling with powder coated exposed G.I. gridsuspension system (E-Grid T 2430 or equivalent load carrying capacity with midspan deflection not exceeding 1/360 span with hanger spacing of 1200mm c/c)consisting of Main Runner 3600 mm long, Cross Tee 1200 mm / 600 mm long andWall Angle. The Wall Angle shall be fixed on PVC Dash Fasteners on theperimeter of the wall by steel screws with distance 300mm c/c. The Main Runnersto be placed @ 1200 mm. The Cross Tee 1200mm will be inserted in the pre-cut slots of Main Runner at a regular interval of 600 mm to form a modular grid of1200mm X 600mm. Additional Cross Tees of 600 mm shall be placedperpendicular to the Cross Tee 1200 mm long to finally form a grid of 600 mm X600 mm. Grid of module size 600 mm X 600 mm shall be supported by 6 mm diaG.I. wire from purlins / soffit. 6 mm thick High Pressure Steam Cured NonAsbestos Fibre Cement Standard Ceiling Board (Density > 1300 Kg/m ³) of size595 mm X 595 mm, conforming IS 14862 & Type B Category III of ISO 8336,tested as per AS-1530 part 3 & BS-476 Part 4,5,6,7 & 8, should be placed in theGrid module to form a False Ceiling. All complete as per the drawing &directions of Engineer-in-charge. (A)In ground floor.A) False Ceiling (with 6mm thick Fibre Cement Designer Board and E-Grid T-2430). 1.52 x 1.52 =2.31m ²	2.310	Sq.M

--	--	--	--