

Feeder Dairy: P.O-Berhampore: PIN -742101: Dist.-Murshidabad e-mail: <u>bhagirathi6@rediffmail.com</u>; website: www.bhagirathimilk.com

BU/MDO/RIDFXXIX/0272

Dated:20.05.2025

Scope of Work	Supply Installation and Commissioning of 1 no(s) of Bulk Milk Cooler having capacity of 10,000 liters.	
Bid Inviting Authority	The Managing Director of The Bhagirathi Cooperative Milk Producers' Union Limited.	
Technical Bid Documents to be furnished by bidder	1. The Company must be an authorized supplier or Service provider of IDMC. Authorization certificate must be submitted.	
	2. ISO, BIS Certificate and Industrial safety certificate must be uploaded. The certificates should be valid on the last date of submission of bid and should remain valid during the tenure of the contract period if work is awarded.	
	3. PAN CARD and GSTIN (GST Registration)	
	4. Minimum Turnover of Rs 15 Crores in each Financial year 2021-2022, 2022-2023, 2023-2024. Audited Balance Sheet of previous three consecutive financial years (2021-2022, 2022-2023, 2023-2024) must be provided. The statement of annual turnover from Chartered Accountant with sign, seal and registration number.	
	5. Supply of minimum 10 no(s) of BMC in the last 3 years. Work Order and Completion Certificate in support of the same must be submitted/uploaded.	
	6. Duly filled Annexure-I.	
	7. The technical team of BCMPUL may inspect the required infrastructure available with the bidder before finalization of the tender.	

DETAILED TECHNICAL SPECIFICATIONS AND SCOPE OF SUPPLY

1. GENERAL DESCRIPTION

Design, supply, installation & Commissioning of direct expansion type of bulk milk cooling system including all accessories & items given in the detailed scope of work.

2. FUNCTIONAL REQUIREMENT.

This system would be installed in village dairy cooperative society (DCS)/village milk collection center which collects the milk every day in the morning & evening from milk producers, The milk collected shall be stored in the bulk milk cooler cooled from ambient temperature to 4^oC. The stored milk shall be dispatched to dairy plant through insulated road milk tanker once in a day.

3. SUPPLY.

The bulk milk cooler shall be a complete unit with the refrigeration system, Agitator, lockable inlet & outlet valve with line strainer (Disc Type) to dump tank outlet. Also includes supply of



Feeder Dairy: P.O-Berhampore: PIN -742101: Dist.-Murshidabad e-mail: <u>bhagirathi6@rediffmail.com</u>; website: www.bhagirathimilk.com

AISI-304 balance tank with SS filter for pumped system SS piping & milk hose unions & milk transfer pump of 12KLPH SS 304 pipes & fittings, food grade quality flexible hose of adequate length. Erection materials, pipe supports, floor plates, pipe clamps, cable conduits shall also be supplied. Earth pit CI covers & earthing as required by local electrical regulation. The indicative distances between SS collection tray to balance tank – 2m, between balance tank to bulk milk cooler – 5 m, BMC to Mains power point – 20m may be considered for calculating cable & SS piping requirement, The exact distances for SS piping, electrical cabling to panels shall be as er site conditions and complete piping & cabling necessary for installation shall be supplied. Power cables should be copper armoured with standard cross-sectional area * required core as per power load requirement.

4. DESIGN REQUIREMENT.

The net capacity of the bulk milk cooler should be as mentioned below; however, the gross capacity in all sizes shall be around 10% higher than the rated capacity to avoid agitation or accidental spillage of milk. Tank capacity 10000 lit.

5. CONSTRUCTIONAL FEATURES.

- I. Material used for construction: Rated capacity 10000 lit. Gross 11000 lit. BMC tank inner, outer, bottom and top open able cover shall be fabricated from stainless steel AISI304 Material. The Skid made from heavy M.S. box section and shall be hot dip galvanized on which refrigeration unit is mounted. All piping, fitting, lockable cover, agitator shaft & blade adjustable ball feet made from AISI304 dipstick, outlet & inlet valves, blank flanges, ladder & manhole of about 45 centimetres diameter for closed type milk cooling tank etc. made from AISI304.
- **II.** Shape & orientation: 10000 lit. Horizontal Cylindrical closed type tank.

6. TANK FITTINGS & ACCESSORIES.

The tank shall be provided with stainless steel inlet with special "no-foam" design, outlet 38mm. butterfly valve & blank union with locking arrangement, a sampling cock lockable type at outlet before butterfly valve, Inspection window/manhole with locking arrangement. The digital type of temperature indicator shall be provided in the control panel. Temperature sensor shall be permanently fixed at the bottom. It shall sense the temperature of the surface at the outlet & transmit the signal to the digital Indicator. The tank shall be provided with S.S. calibrated dipstick to measure the volume of milk inside the tank. The dipstick shall be graduated from 10% or less to not less than 100% of the rated volume. The tank shall be equipped with agitator capable of producing a uniform distribution of fat in the milk.

All S.S. Fittings shall be of SMS STANDARD.

BMC shall be provided with AISI-304 filter with SS fine wire mesh. The filter shall be designed and installed in such way that it can frequently and easily be cleaned.

Looking Arrangement/ Inspection window



The Bhagirathi Co-op. Milk Producers' Union Ltd. Feeder Dairy: P.O-Berhampore: PIN -742101: Dist.-Murshidabad e-mail: <u>bhagirathi6@rediffmail.com</u>; website: www.bhagirathimilk.com

Should be of glass and lighting system for easy viewing of the milk in tank and the dip stick in the tank.

7. INSULATION.

The insulation of the tank shall be done by injection in-situ of high density 40kg/m³ CFC free polyurethane foam and the thickness should be at least 70mm. the efficient of the insulation should be such that at max. 50°C ambient temperature the rate of rise of the mean temperature of the milk shall not exceed by 1°C in 4 hrs when the rated milk volume initially at about 4°C is allowed to stand undisturbed when refrigeration unit is not working.

8. CLEANING IN PLACE (CIP).

For closed type tank configuration facilities for cleaning-In-Place shall be provided which shall include CIP spray balls and piping from milk reception / balance tank through milk transfer pump to bulk milk cooler. Using Balance Tank, Rotating dish and nozzle spray system in the tank to cover all the internal surface of the tank. Minimum 3 nozzle spray must be provided.

9. TANKER LOADING ARRANGMENT:

1000-liter capacity Stainless Steel balance tank should be provided with 10000 Lit capacity Bulk Milk Cooler. From BMC the Milk shall be transferred to road milk tanker (RMT) through food grade quality flexible hose of adequate (min 10 m) length. SS304 Pipes of 38mm size will be provided from the Balance tank via in-line filet & Milk Transfer by pump up to BMC. Balance tank should be provided with 38 mm stop valve 38mm 55 no(s) piping for 10 KL BMC should be min. 25m with MS bend & unions fittings 4 valves. 38mm SMS union-min. 12 no(s), bends min.- 8 no(s), Supports min -12 no(s).

10. REFRIGERATION SYSTEM

The refrigeration system shall be designed to comply with ARI Standard 520 -2004 & to meet the requirements of the milk collection system of ISO 5708, class II. The refrigeration system shall be of direct expansion type with R404a or CFC free, environmentally friendly refrigerant to cool the raw milk from reception temp. to 4°C in the prescribed period mentioned. The evaporators of the system shall form a part of the milk tank body as dimpled jacket in the bottom plate in case of rectangular open tank or at least up to 1/3 height of circular closed tank. The refrigeration system shall be direct expansion type to perform cooling function in an ambient temperature of 46°C with air cooled condenser.

I. COMPRESSOR

The refrigeration compressor shall be adequate to ensure that milk is cooled to 4°C. In the prescribed time limit & suitable to operate at 0°C Suction temp & 60°C condensing temperature (air cooled condenser) assuming 46°C ambient Temperature. The refrigeration compressor(s) shall be energy efficient hermetically sealed reciprocating/scroll. The compressors selected should be energy efficient consume least power to meet the cooling load requirements.

II. CONDENSER



The condenser shall be air cooled finned tube type having sufficient heat transfer area designed for extremely high ambient temperature given above.

III. RECEIVER

For refrigeration circuit a suitable size liquid receiver mounted on the skid near compressor to assist system to store refrigerant during pump down cycle as well as in case of maintenance.

IV. THERMOSTATIC EXPANSION VALVE

Suitable size & capacity Thermostatic expansion valve should be provided in the refrigeration circuit of the bulk milk cooler. TX valve should be maximum operating pressure type and of adequate capacity to feed optimum of refrigerant to the milk cooling tank evaporator.

V. REFRIGERANT PIPE, FITTING AND CONTROLLER

All pipes, valves, fittings & controls shall comply with the latest relevant BIS code applicable. Isolation valves at suction & discharge sides of compressors is provided for compressor isolation, during maintenance of the system All the pipes shall be clamped properly with fixed support. In case of double compressor system, pipe fitting & control should be designed in such a way that both the compressors can run independently. The tubing shall be insulated wherever necessary.

11. ELECTRICAL CONTROL PANNEL

I. Control Panel

Three control panels shall be provided, one for the main power supply tapping, second for the refrigeration unit and third for the milk tank. Each panel shall be provided with MCBs of suitable ratings for switching and protection as per the system requirement. The incoming and outgoing power supply terminals shall be covered and secured with a lead seal to prevent tampering. The door of the panels should be provided with lockable handles.

II. Main Control Panel

This panel should be suitable to tap the incoming State Electricity Board supply and feed the refrigeration unit, agitator motor and milk unloading pump (from balance tank) and dispatch pumps. It should be provided with necessary phase indication lamps (LED type), contactors, MCBs, ammeter, voltmeter, energy-meter, frequency-meter, push buttons etc.

Note: The switch gears, contractor, relays, used in all the panels should be of reputed makes. L & T / Siemens/ ABB make.

III. Refrigeration Control Panel

The panel shall be provided with motor starters, ON/OFF push buttons & necessary MCBs, control wiring, line voltage controller to guard the compressor is provided in the refrigeration system, the control panel shall be provided with a sequence controller & timer to start one compressor at a time to avoid power supply surge. The panel shall also have facility to operate



Feeder Dairy: P.O-Berhampore: PIN -742101: Dist.-Murshidabad e-mail: <u>bhagirathi6@rediffmail.com</u>; website: www.bhagirathimilk.com

refrigeration unit on auto/ manual mode. As soon as the milk temperature reaches to pre-set value, the compressor should be switched off to avoid freezing of milk.

12. Voltage Stabilizer (Servo type) and single-phase preventer:

The system should have Voltage stabilizer conforming to following features and single-phase preventer of suitable rating individually correct the voltage of each phase. Auto low – high cut out. Phase sequence Preventer. Stabilizer should be supplied as per BMC load (electrical) capacity.

13. Cables & Electrical Switch gears.

All electrical switchgears, controls & electrical cables required for the complete system shall be of suitable rating & of standard company. All cables flexible or armored should be as per site measurement & site load. Switch make Copper armored cable should be provided from MSEB meter to stabilizer & Stabilizer to generator minimum 30m of specific size & above if required as per site condition.

14. EARTHING

The earthing should be carried as per IS: 3043-1987(reaffirmed 2001) "code of practice for earthing". The chassis, framework and the fixed parts of the metal casing of the tanks where used shall be provided with two separate earthing terminals, Earthing for Alternator & Panels. The earthing terminals shall be of adequate size, be protected against corrosion and shall be metallically clean. Under no circumstances shall a movable part of the enclosure be insulated from the part carrying terminal when the movable part is in place. The earthing terminal shall be identified by means of the "[]" marked in a legible and indelible manner on or adjacent to the terminals.

15. INSTALLATION

The installation work should be carried in best workman like manner in conformity to the relevant codes of practices of BIS standards applicable for mechanical & electrical installation. Installation shall take place in Murshidabad district in Domkal block in Murshidabad District.

16. COMMISSIONING

Supplier should arrange commissioning & performance trial runs of the bulk milk cooling system to the satisfaction of the client The supplier shall supply all the consumables required during commissioning of the plant.

17. TOOLBOX

A GI sheet toolbox containing one set of all necessary tools required for regular maintenance of the unit shall be supplied along with the BMC. 1000-1400 RPM blower - 1No.

18. MANUAL

One sets of operation & maintenance manual, containing complete details of starting uo, putting off, critical checks and day to day maintenance of the complete system shall be supplied. The manual should also have the required electrical circuit diagrams.

19. FIRE EXTINGUISHER:



Feeder Dairy: P.O-Berhampore: PIN -742101: Dist.-Murshidabad e-mail: <u>bhagirathi6@rediffmail.com</u>; website: www.bhagirathimilk.com

BMC should have fire extinguisher with unit.

20. DIP STICKS:

Facilities to measure Milk Quantity SS Dip sticks of AISI304 with calibrated chat.

21. WATER HEATER (Geyser):

Instant Electric water of capacity heater 20 Liters with suitable output capacity of hot water with each BMC (with ISI mark).

Sd/-

Managing Director The Bhagirathi Cooperative Milk Producers' Union Limited



Feeder Dairy: P.O-Berhampore: PIN -742101: Dist.-Murshidabad e-mail: <u>bhagirathi6@rediffmail.com</u>; website: www.bhagirathimilk.com

TECHNICAL SPECIFICATION FOR 10000 LIT CAP BMCU MILK TANK:

SL. NO.	DESCRIPTION	DETAILS
А	MILK TANK AND EQUIPMENTS	CYLINDRICAL HORIZONTAL CLOSED TYPE
1.	Capacity-Net	10000 Liters
2.	Capacity-Gross	11000 Liters
3.	MOC	AISI SS 304
4.	Туре	Completely closed type in Shape of Elliptical Horizontal
5.	Overall Surface finished	Minimum 220grits/ Pvc coated, 2B Finished.
6.	Overall Weight	As per ISO-5708 Type 2A II (Latest Version) Standard
7.	Thickness -Inner shell -Outer shell	As per ISO-5708 Type 2A II (Latest Version) Standard 1.6 MM
8.	Overall Dimension	As per ISO-5708 Type 2A II (Latest Version) Standard
9.	CIP Facility	Using Balance Tank and Rotating Disc & Nozzle Spray System in tank to cover all the internal surface (Min 3 Nozzle Spray).
10.	No. of Agitator	2(Two)
11.	RPM of Agitator	21-30
12.	Type of Insulation	By injection in situ of high density (Min. 40Kg/m ³) CFC free Polyurethane Foam without any imperfection and Hygroscopicity.
13.	Thickness of Insulation	70 mm or as per specified NDDB/IS Standard.
14.	Density of insulation	40Kg/ m ³
15.	Facilities to measure Milk Quantity	SS Dipsticks with Laminated calibrated chart or digital dipstick.
16.	Manhole cover	SS304 with SS fastening. Insulated cover with rubber gasket & locking arrangement.
17.	SS 3-way plug valves, Pipes, Support for Clamping of SS Line, SS bends & unions.	Pipe clamp should be of SS304 with wingnut and support to be given from sealing and support material should be of SS 304 pipe (38 mm) and clamp as per required. Hose pipe hanging hooks.
18.	Milk Pump	IDMC/ Alfa Laval/ Fristamp/ Swastik / Zeutech make 3HP three phase with outlet 51 mm having SS shroud Impellerand body also SS304, with adjustable legs coupled with motor (Min rate flow 12KLPH) L&T Make Dol Type starter having relay of suitable range to be provided.
19.	Tank Leveling	The tank shall be with adjustable ball feet to adjust the level as per ground surface at location.
20.	Ladder	Suitable SS304 quality ladder shall be provided with the tank to enter the tank for manual cleaning when needed. Or manual cleaning arrangements as designed by the company.



Feeder Dairy: P.O-Berhampore: PIN -742101: Dist.-Murshidabad e-mail: <u>bhagirathi6@rediffmail.com</u>; website: www.bhagirathimilk.com

21.	Inner Vessel	All inner joints should be TIG welding and attachments should have finish not less than 150 grit. Proper welded with no sharp edges to avoid contamination.
22.	Filter	AISI 304 SS fine wire mesh (Dish type)
23.	Tank & Pipe cleaning Brushes	One Tank cleaning brush & one 1800mm long pipe cleaning brush.
24.	SS Pipeline	AISI SS 304 Quality non-welded all pipelines should be 51mm. All pipeline joints shall be fitted with SMS Union.
25.	Inspection Window/ Locking Arrangement	Provided clear, direct view of the milk level inside the tank. Window should be made of transparent glass, food grade Acrylic or tempered glass & lighting system for easy viewing of the milk & dipstick inside the BMC. Window should be generally located on the side of the BMC at an optimal height to observe the milk level without opening the lid.
26.	Spare & Tools	 51mm SMS union - 04 nos 51 mm bend - 02 nos 51 mm T - 02 nos 51mm Butterfly Valve - 01 nos 51mm 3way valve - 01 nos C Spanner - 01 nos 51mm rubber hose pipe (food grade) - 12 mtr All items should be provided. A GI sheet box containing one set of all necessary tools required. 1000 to 1400 RPM blower (Heavy duty) - 01 nos One fire extinguisher set.



Feeder Dairy: P.O-Berhampore: PIN -742101: Dist.-Murshidabad e-mail: <u>bhagirathi6@rediffmail.com</u>; website: www.bhagirathimilk.com

В	REFRIGERATION	3 PH, 2 CU (ARI Standard 520 - 2004)
1.	Туре	Direct Expansion
2.	Make of Compressor	Emerson hermetically sealed scroll Type (4 no. Compressor)
3.	Model	ZB48 Suitable to meeting the cooling time 3 hour to bring down the Milk temp from 35 to 4°Cas per ISO 5708 2AII norms.
4.	Type of Refrigerant	R404a
5.	Cooling capacity of compressor, R-22	22000 Kcal/hr at 0 °C Evaporating temperature and 55 °C condensing temperature.
6.	Cooling capacity of condenser, R-22	38640 Kcal/hour at Ambient Temp.
7.	Make of Condenser	Emerson
8.	Model of Condenser	Copper Construction Fin & Tube Type
9.	No. of Condenser	4
10.	No. of Fans	8(Eight) 18" sweep Dia. Easily repairable*
11.	Thermostatic Expansion Valve	8 Lit * 4 nos.
12.	Thermostatic Expansion Valve, make.	Emerson, MOP
13.	Control Panel	Refrigeration Panel body should be made by SS sheet. Automatic cut off & restart system, Digital temperature controller, Auto & Manual facility, digital voltage & Amp meter, Emergency stop switch, HP & LP trip system, ON Delay & OFF Delay timer, Single phase cut off system should be provided.
С	DESIGN PARAMETERS	
1.	standards	ISO 5708/2A II
2.	Ambient temp.	48 °C
3.	Maximum Cooling time for Ist milking	3 hour, 35 to 4 °C
4.	II nd milking	1.5hour, 10 to 4 °C
5.	Safe Operating Temp.	43 °C
D	VOLTAGE STABILIZER	SERVO CONTROLLED SINGLE PHASE
1.	Make & Capacity	ASABA/Luminous/ABB India/Globe : 100 KVA
2.	Input Voltage	340V- 480V
3.	Out Voltage	415V
4.	Protection	 High/Low voltage output cut off Over load Protection Short Circuit Protection By-pass Arrangement* Single Phasing* Noise Filtering Phase Failure Relay- VSPD2 * Input/ Output Volt Meter on GEB and DGSet



Feeder Dairy: P.O-Berhampore: PIN -742101: Dist.-Murshidabad e-mail: <u>bhagirathi6@rediffmail.com</u>; website: www.bhagirathimilk.com

Е	ELECTRIC CABLE AND ELECTRICAL SWITCH GEARS	 Cable should be of Polycab / Finolex supply cable from DG set to stabilizer should be of 10 sq.mm x 4 core and supplier will have to provide also cable of 10 sq.mm x 4 core copper armoured cable from GEB Meter to Wall mount change over switch. Cable Laying should be in conduit pipe. Cable 30 meter in supplier scope. Switch gears make - L&T/ SEIMENS / ABP.
F	EARTHING AS PER I.E STANDARD	 It should be carried as per IS:3043 - 1987 (reaffirmed 2001) - "Code of practice for earthing". Earthing as per comprising of following: 1. Earthing plate would be of Galvanized Iron plate 2. Earth pit would be 3m deep 3. Distance between two plate would be at least 1.5m 4. Earth Link test would be carried out and should be less than 1 ohm. 5. Total earthing 4 no(s) for BMC* 6. Total earthing 3 no(s) for DG* 7. Earthing connection to BMC Unit, Control panel & Stabilizer shall be through GI earthing strips.
G	ADDITIONAL REFRIGERATION SPARES TO BE SUPPLIED	Thermostatic Expansion Valve, Dryer Filter, High- & Low- pressure tripping safety switch. 2 sets for each BMC unit must be supplied.

- The Goods supplied under this Contract shall conform to the standards mentioned in the Technical Specifications, and when no applicable standard is mentioned, to the latest Indian Standards.
- In any case there is a confusion regarding specification, the supplier must quote the rate as per BIS/NDDB Specification.

Sd/-

Managing Director The Bhagirathi Cooperative Milk Producers' Union Limited



GENERAL TERMS & CONDITIONS

- 1. The documents submitted by the bidders should be properly indexed & digitally signed.
- 2. During the scrutiny, if it comes to the notice to the tender inviting authority that the credential(s) and/or any other paper(s) has/have been of any bidder found incorrect/ manufactured/ fabricated, that bidder will not be allowed to participate in the tender process and that application will be rejected outright. The Bhagirathi Cooperative Milk Producers' Union Ltd. Reserves the right to cancel the N.I.T. at any time without showing any reason and no claim in this respect will be entertained.
- 3. During evaluation the Committee may summon any bidder and seek clarification/information regarding bids within the stipulated time frame. In case the bidders fail to clarify any query during the stipulated time frame the bid shall be liable for rejection.
- 4. The Milk Union may reject any bid from any party with unsatisfactory performance with the Milk Union or any other Milk Union in the past.
- 5. Inspection of materials may be undertaken at the supplier's premises whenever necessary by the Tendering Authority/ any officer authorized by the undersigned.
- 6. For 'prompt after sale service' of the installed unit as and when required within warranty period free of cost. The service must be attended within 24 hours from the receipt of the information.
- 7. Bidders are required to go through the Tender Documents understand the requirement the location of the installation and commissioning and then quote their rate. Rate once quoted by the bidder shall be deemed to be quoted by the bidder after understanding the requirements of the Milk Union. Rates once quoted are final and no alteration in rate shall be allowed. All the pages of this NIT must be duly signed, sealed and uploaded by the bidder as a token of acceptance of the Terms and Conditions of the NIT.
- 8. **Price:** Price charged by the supplier for goods delivered under the contract shall not vary from the prices quoted by the supplier in its bid. Price consists of the cost of the equipment along with installation and commissioning of the unit along with trial run and satisfactory operational training of the entire unit with 3 years of comprehensive warranty along with all taxes and levies.
- 9. **Bid Validity**: The rate once quoted in this tender shall remain valid for a period of 365 days from the date of Financial Bid Evaluation. Bidders are therefore required to assess their rates before quoting them.
- 10. **Warranty**: All the spares and components of the BMC Set must be warranted by the supplier for a period of 3 years from the date of successful installation and commissioning. If any component is found to be non-functional due to any manufacturing defect or as a result of poor workmanship the component must be immediately replaced by the supplier within 24 hours free of cost and the replaced spare should have the warranty period of 3 years.

Warranty Extension: The warranty of equipment would be extended if equipment remains down during the warranty period, for more than period mentioned below: -

• If any major equipment has been down for more than 10 days in a year, warranty would be extended by one Month.



- If any major equipment has been down for more than 30 days due to malfunctioning of the any part supplied by supplier or want of spares/ consumable, warranty would be extended by 1 Year.
- 11. **Payment**: Payment shall be released in 3 phases in NEFT/RTGS to the Bank Account of the supplier after submission of 3 copies of invoice along with documents mentioned in documentation clause which are as follows:
 - a. **First Phase**: 70% payment shall be released within 1 month of successful delivery of the entire Unit in good condition certified by the Concerned Official and approved by the Competent Authority. EMD shall also be released after receipt of intimation in writing from the supplier.
 - b. **Second Phase**: 20% payment shall be released after successful installation and commissioning of the entire Unit certified by the Concerned Official and approved by the Competent Authority.
 - c. **Third Phase**: 10% payment shall be released after 3 months of submission of equivalent amount of bank guarantee valid for a period of 3 years. This shall serve as Performance Guarantee. In case the party fails to provide maintenance and support as per the requirement of the Milk Union or is found to act in a way which jeopardizes the operations of the Milk Union, the Performance Bank Guarantee shall be forfeited after giving a Notice to the supplier in writing and the supplier shall be debarred from participating into any tender in future.
- 12. **EMD & Security Deposit**: EMD shall not carry interest. EMD of unsuccessful bidders shall be refunded within 2 working days after finalization of Award of Contract. EMD of the successful bidder shall be converted into Security Deposit and shall be released along with the first phase of payment.
- 13. **Insurance:** The supplier shall make arrangements for insuring the goods against loss or damage incidental to manufacture or acquisition, transportation, storage and delivery. If the equipment's is not commissioned and handed over to The Bhagirathi Co-Operative Milk Producers Union Ltd. within specified period, the insurance will have to be extended by the supplier at their cost till the successful installation, testing, commissioning and handing over of the goods to The Bhagirathi Co-operative Milk Producers' Union Ltd.
- 12. **Penal Measure**: Time being the essence of the contract, failure to supply the materials within due time or delay in installation and commissioning of the materials shall invite penalty.
 - I. Liquidated damages of 0.5% per week subject to a maximum of 10% of the total cost of materials shall be charged if goods are not delivered installed or commissioned in time and the amount will be deducted from the Security Deposit and bills submitted by the supplier.
 - II. For violation of any terms and conditions of the contract the Bhagirathi Milk Union reserves the right to cancel the contract without assigning any reason thereof. On termination of Contract the Security Deposit will be forfeited and the resultant loss shall be recovered from the company. The subsequent company will be blacklisted for 3 years.
- 13. **Unloading** of goods is the responsibility of the Milk Union. The party shall communicate well ahead in advance before dispatch of material.
- 14. **Site Preparation:** Preparation of site for installation and commissioning the Unit shall be arranged by the Milk Union.



- 15. **Documentation**: Complete documentation like principal warranty papers, operation manuals, document of technical specifications and guarantee cards must be furnished by the supplier. Failure to submit any of the above documents in hard copies at the time of supply of the materials shall lead to non-acceptance of the material.
- 16. **Delivery, Installation and Commissioning**: The materials must be delivered installed and commissioned in Domkal block in Murshidabad district in West Bengal. The installation and commissioning of the unit must be completed within 60 days from the acceptance of the Purchase Order. It is critically important to coordinate with the Milk Union before dispatch of materials.
- 17. **Inspection:** BMC unit after delivery are subject to inspection at dairy plants before acceptance. If rejected due to any defect, deficiency transit damage or wrong supply, the report of our inspector in this respect shall be final and no correspondence on the subject would be entertained. The rejected goods should be removed from our premises by the Supplier within 15 days after receipt of our inspection report.
- 18. **Standards:** The Goods supplied under this Agreement shall conform to the standards mentioned in the Technical Specifications and when no applicable standard is mentioned, to the authoritative standards appropriate to the Goods' to the latest Indian Standards.
- 19. **Registration of Goods:** If required under the Applicable Law, goods supplied under the Agreement shall be registered for use in India.
- 20. **Patent Rights:** The Supplier shall indemnify the Purchaser against all third-party claims of infringement of patent, trademark, or industrial design rights arising from use of the Goods or any part thereof.
- 21. **Packing:** The Supplier shall provide such packing of the Goods as is required to prevent their damage or deterioration during transit to their final destination, as indicated in the Purchase Order.
- 22. **Termination for Default:** The Purchaser, without prejudice to any other remedy for breach of the Agreement, by written notice of default sent to the Supplier, may terminate this Agreement in whole or in part:
 - a) If the Supplier fails to deliver any or all of the Goods within the period(s) specified in the Purchase Order, or within any extension thereof granted by the Purchaser; or
 - b) If the Goods do not meet the Technical Specifications or registration requirement (if any) stated in the Agreement; or
 - c) If the Supplier, in the judgment of the Purchaser has engaged in fraud and corruption, in competing for or in executing the Agreement; or
 - d) If the Supplier fails to perform any other obligation(s) under the Agreement.



- 23. **Termination for Insolvency:** The Purchaser may at any time terminate the Agreement by giving written notice to the Supplier if the Supplier becomes bankrupt or otherwise insolvent.
- 24. **Termination for Convenience:** The Purchase, by written notice sent to the Supplier, may terminate the Agreement or the Purchase Order, in whole or in part, at any time for its convenience. The notice of termination shall specify that termination is for the Purchaser's convenience, the extent to which performance of the Supplier under the Agreement or Purchase Order is terminated, and the date upon which such termination becomes effective. The Goods that are already supplied before the Supplier's receipt of notice of termination shall be accepted by the Purchaser at the terms and prices described in the Agreement and the Purchaser order.
- 25. **Dispute Resolution:** Any dispute arising out of the Agreement, which cannot be amicably settled between the parties, shall be referred to adjudication/arbitration in accordance with the Arbitration and Conciliation Act of 1996 of India. The venue of adjudication/arbitration shall be Kolkata. The language of arbitration shall be English.
- 26. **Agreement:** The supplier must be free to execute an agreement embodying the terms and conditions of the Tender Notice
- 27. **Applicable Law:** The Agreement shall be interpreted in accordance with the laws of Union of India.
- 28. **Force Majeure:** If, at any time during the subsistence of this contract, the performance in whole or in part by either party of any obligation under this contract is prevented or delayed by reasons of any war or hostility, act of public enemy, civil commotion, sabotage, fire, floods, explosion, epidemics, quarantine restriction, strikers lockout or act of God (hereinafter referred to as events) neither party shall have any claim for damages against other in respect of such non-performance or delay in performance.
- 29. The undersigned reserves the right to accept or reject any tenders and to cancel the entire tender process at any point of time without assigning any reason thereof.

Sd/-Managing Director The Bhagirathi Cooperative Milk Producers' Union Limited



Feeder Dairy: P.O-Berhampore: PIN -742101: Dist.-Murshidabad e-mail: <u>bhagirathi6@rediffmail.com</u>; website: www.bhagirathimilk.com

<u>ANNEXURE – I</u>

Declaration by the bidder

(To be furnished in the letterhead of the Bidder)

- 1. I/We the undersigned solemnly declare that all the statements made in the documents, records etc., attached with this application are true and correct to the best of my/our knowledge.
- 2. I/We the undersigned do hereby certify that neither my/our firm/company nor any of its constituent partners have abandoned any work/works of similar nature and magnitude in India, in the past.
- 3. I/We the undersigned do hereby certify that any of the contracts awarded to me/us has not been terminated rescinded, due to breach of contract on my/our part in the past.
- 4. I/We the undersigned do hereby certify that we have not been blacklisted by any organization/NDDB/Milk Union/Milk Federation in the past.
- 5. I/We the undersigned authorize (s) and request any bank / person / firm / corporation / Government Departments to furnish pertinent information deemed necessary and requested by The Bhagirathi Cooperative Milk Producers' Union Ltd. to verify the statement made by me/us or to assess my/our competence and general reputation.
- 6. I/We the undersigned, understand(s) that further qualifying information / clarifications on the statement made by me / us may be requested by The Bhagirathi Cooperative Milk Producers' Union Ltd and agree(s) to furnish such information/clarification within SEVEN Days from the date of receipt of such request from The Bhagirathi Cooperative Milk Producers' Union Ltd.
- 7. I/We agreed to execute a formal Agreement embodying the terms & conditions of the said online tender and the General Terms & Conditions.

Dated Signature of Authorized Signatory of the Company with Seal: